



Tiger Waterfront Products, LLC.

35 Cooperative Way
Wright City, MO USA 63390
www.tigerdocks.com
tel 1-636-745-7003
fax 1-636-745-7047

SALES ORDER

order # SO-011252
date 10/2/2020

billing address **Pinnacle Lake Estates**
102 Skyline Drive South
New Florence, MO
USA
63363

shipping address **Pinnacle Lake Estates**
102 Skyline Drive South
New Florence, MO
USA
63363

contact Carley Lewis
phone 618-410-3744

sales rep
Jason

payment terms
Due at Installation

ITEM	DESCRIPTION	QUANTITY	UNIT PRICE	SUB-TOTAL
MATERIAL	MATERIAL --- Material to correctly anchor Pinnacle Lake North and South Marina Docks. INCLUDES --- Adding two more corner gussets to the middle of the South Dock and two corner gussets to the middle of the North Dock to match those added to the end of South Dock last year. They will include gussets, #11 Winches, Winch Stands and Fairleads. We will re-use the two 30 gallon anchors that are currently in seperate locations, and move them to use as one anchor to the south side of the south dock. We will drop two new 5 - ton anchors (one in the middle of the two docks and one to the North of the North Dock. We will connect both the North and South docks to the anchor set in the middle of the docks and the North Dock to the anchor dropped to the North. Reusing the current anchors and using one for both in the middle will save costs of adding two additional docks for those locations. - MATERIAL - Two Concrete Anchors, 4 total (Corner Gussets with Fairleads and Winch Stands, 4 total (#11 Winches, All Stainless Steel Cable, Screw Pin Shackels, Heavy Duty Stainless Thimbles, Cable Clamps, all Hardware and Fasteners.	1	\$9,557.90	\$9,557.90
Misc. Labor	CREW LABOR --- Labor and equipment costs to drop concrete anchors, attach corner gussets, run calble to winches and complete shore anchoring.	1	\$4,560.00	\$4,560.00

remarks Notes:
50% deposit required to get on schedule and start fabrication of anchoring components.

SUB-TOTAL \$14,117.90
TAX 1 \$759.85
TOTAL \$14,877.75